



**ADDENDUM NO. 1
to the
CONTRACT DOCUMENTS, SPECIFICATIONS and DRAWINGS
FOR
WSU PULLMAN, WA
TAPUS 2038(049) ORCHARD DRIVE PATHWAY**

June 18, 2024

All bidders shall acknowledge receipt of this addendum by acknowledgment on the Local Agency Proposal – Signature Page (DOT Form 272-036K).

All changes, corrections, deletions and/or additions to the initial bidding documents enumerated herein shall be a part of the bidding documents. In case of any conflict between the drawings, specifications, and this Addendum, this Addendum shall govern.

BID DOCUMENTS

DRAWINGS

C-104, Keyed Note 30 shall read:

INSTALL NEW CATCH BASIN FRAME AND GRATE AND ADJUST TO FINISH GRADE; RE: CITY OF PULLMAN STD WSG NO 13/C-510, WSDOT STD BID ITEM 3091

BID SCHEDULE

The Bid Schedule has been updated to remove the item 3100 – Adjust catch basin. All catch basins that are to be impacted are removed/replaced with new catch basins per WSDOT Standard Bid Item #3091.

Contractor shall use revised BID SCHEDULE (attached).

CLARIFICATIONS (Q: Question; A: Answer)

Q: Confirm that existing catch basins are to be removed and replaced with WSDOT type 1 catch basins. There are currently no demolition notes for these structures.

A: All 3 catch basins to be removed/replaced as shown on C-103 and C-104 are WSDOT Type 1 catch basins with combination frame/grate per details. See change to C-104 listed above showing replacement of catch basin at NE Cove Way.

Q: Please provide existing storm drainpipe sizing, type, and invert elevations.

A: Based on Topo survey starting from north end (material for piping unknown, but assumed as PVC or concrete per City of Pullman mapping):

**Catch Basin (STA 14+57.16 east side) – not being impacted
Rim = 2562.65
8"IE=2559.80 (material unknown)**

Catch Basin (STA 10+50.94 west side)



Rim = 2597.33
8" IE = unknown (PVC)

Catch Basin (STA 10+56.59 east side) – not being impacted
Rim = 2597.19
8"IE=2594.39 (material unknown)
8"IE=2594.19 (material unknown)

SDMH (STA 10+58.05 east side) – adjust to finish grade
Rim = 2597.93
8"IE(W)=unknown (material unknown)
12"IE(N)=2594.19 (material unknown)

Catch Basin (STA 5+17.92 west side)
Rim = 2591.12
8"IE=2589.25 (material unknown)

Catch Basin (STA 5+32.30 east side)
Rim = 2592.83
IE=not visible, plugged, standing water = 2590.93

Q: Please provide the Engineers Estimate for this contract.

A: The engineer's opinion of probable cost for the base bid is approximately \$489,300

Prepared by Angela J. Taylor
KELLER ASSOCIATES, INC.

Bid Schedule: Repair/Replace Sidewalk/Pathway Along Orchard Dr.

WSDOT Bid Item #	Bid Item	Unit	Cost Per Unit	Base Bid Quantity	Base Bid Cost
BASE BID					
0001	MOBILIZATION	LS		10%	
0025	CLEARING AND GRUBBING	ACRE		0.3	
0050	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS		1	
0080	REMOVING BITUMINOUS PAVEMENT	SY		745	
0100	REMOVING CEMENT CONC. SIDEWALK	SY		1,207	
0108	REMOVING CEMENT CONC. CURB AND	LF		240	
0187	REMOVING PAINT LINE	LF		150	
0220	REMOVING CHAIN LINK FENCE	LF		25	
1171	DRAIN PIPE – 8" DIA	LF		35	
3080	ADJUST MANHOLE	EA		2	
3091	CATCH BASIN TYPE 1	EA		3	
5095	CRUSHED SURFACING BASE COURSE	CY		284	
5767	HMA CL. 1/2 IN. PG 64H-28	TON		243	
6488	EROSION CONTROL AND WATER POLLUTION PREVENTION	LS		1	
6700	CEMENT CONC TRAFFIC CURB AND GUTTER	LF		429	
6701	CEMENT CONC. TRAFFIC CURB	LF		72	
6857	PLASTIC CROSSWALK LINE	SF		288	
6859	PLASTIC STOP LINE	LF		21	
6890	PERMANENT SIGNING	LS		1	
6942	CONDUIT PIPE 1 IN. DIAMETER	LF		1,420	
6971	PROJECT TEMPORARY TRAFFIC CONTROL	LS		1	
6980	FLAGGERS	HR		80	
6982	CONSTRUCTION SIGNS CLASS A	SF		149	
7572	WORK ZONE SAFETY CONTINGENCY	EST		5000	
7038	ROADWAY SURVEYING	LS		1	
7042	ADA FEATURES SURVEYING	LS		1	
7043	ADJUST JUNCTION BOX	EA		3	
7055	CEMENT CONCRETE SIDEWALK	SY		226	
7058	CEMENT CONC. CURB RAMP	EA		11	
7059	CEMENT CONC. DRIVEWAY ENTRANCE	SY		55	
	RECORD DRAWINGS	LS		1	\$1,000.00

Repair/Replace Sidewalk/Pathway Along Orchard Dr.
Washington State University - Pullman
Keller Associates, Inc.

SP-200	SEEDING, IRRIGATION AND LANDSCAPING RESTORATION	LS		1	
TOTAL BASE BID AMOUNT (including tax)					
(Total in Words)					

WSDOT Bid Item #	Bid Item	Unit	Cost Per Unit	Base Bid Qua	Base Bid Cost
BID ALTERNATE #1 – LANDSCAPING IMPROVEMENTS					
SP-200	BID ALTERNATE #1: LANDSCAPING & IRRIGATION	LS		1	
TOTAL BID ALTERNATE #1 AMOUNT (including tax)					
(Total in Words)					

WSDOT Bid Item #	Bid Item	Unit	Cost Per Unit	Base Bid Qua	Base Bid Cost
BID ALTERNATE #2 – WALKWAY LIGHTING IMPROVEMENTS					
SP-300	WALKWAY LIGHTING IMPROVEMENTS	LS		1	
TOTAL BID ALTERNATE #2 AMOUNT (including tax)					
(Total in Words)					